

A variationally computed line list for hot NH₃

S. N. Yurchenko,¹ R. J. Barber² and J. Tennyson²*

¹Technische Universität Dresden, Institut für Physikalische Chemie und Elektrochemie, D-01062 Dresden, Germany

²Department of Physics and Astronomy, University College London, Gower Street, WC1E 6BT London

Accepted 2010 December 22. Received 2010 November 5

ABSTRACT

We present ‘BYTe’, a comprehensive ‘hot’ line list for the ro-vibrational transitions of ammonia, ¹⁴NH₃, in its ground electronic state. This line list has been computed variationally using the program suite TROVE, a new spectroscopically determined potential energy surface and an *ab initio* dipole moment surface. BYTe, is designed to be used at all temperatures up to 1500 K. It comprises 1138 323 351 transitions in the frequency range from 0 to 12 000 cm⁻¹, constructed from 1373 897 energy levels below 18 000 cm⁻¹ having *J* values ≤36. Comparisons with laboratory data confirm the accuracy of the line list which is suitable for modelling a variety of astrophysical problems including the atmospheres of extrasolar planets and brown dwarfs.

Key words: molecular data – subdwarfs – infrared: planetary systems.

1 INTRODUCTION

Ammonia is the main nitrogen-containing molecule observable in a variety of astrophysical environments. For example, whilst the spectra of M and L-type brown dwarfs are dominated by H₂O, and CH₄ becomes increasingly important at lower temperatures, NH₃ is a significant source of opacity in the atmospheres of late T-type dwarfs, particularly in the 10.5-μm region (Burrows et al. 1997; Sharp & Burrows 2007). Modelling suggests that absorption by ammonia will be even more important in the yet-to-be discovered Y-dwarfs (Burrows, Sudarsky & Lenine 2003), and it is possible that NH₃ absorption bands may be the principal distinguishing feature of this new class of ultra-cool dwarf.

The molecule is known to be present in the atmosphere of Solar system gas giant planets (Lara et al. 1998). For example, emission spectra of hot ammonia were observed in the atmosphere of Jupiter after the impact of Comet Shoemaker-Levy 9 (Orton et al. 1995) and in the aftermath of the 2009 July impact on Jupiter (Fletcher et al. 2011; Orton et al. 2011).

NH₃ is present in cometary comae, typically in number densities ~0.5 per cent of that of gaseous H₂O (Kawakita & Watanabe 2002; Bonev et al. 2009). Although the cometary environment is cold, solar pumping (Dello Russo et al. 2004; Kawakita & Mumma 2011) and other excitation mechanisms (Barber et al. 2009) are able to excite high-lying ro-vibrational molecular states that in conditions of thermal equilibrium would only be significantly populated at temperatures in the region of 2000 K or higher. In the densities that exist in the coma, these states are able to decay radiatively before being collisionally de-excited, and spectral lines originating

from these highly excited states give important clues to the physical processes at work in cometary comae. The Einstein A coefficient listed in BYTe will enable the measured intensities of cometary NH₃ spectral lines to be used in modelling the conditions in the coma.

Ammonia masers are also observed. These also involve transitions between high-lying states (Madden et al. 1986). Modelling maser action requires significant spectroscopic data, and this too can be provided by our line list, which we call BYTe.

An exciting new area of astronomy is the characterization of extrasolar planets. Water and methane have already been shown to be present in exoplanet atmospheres (for example in HD 189733b; Tinetti et al. 2007; Swain, Vasisht & Tinetti 2008), but to date NH₃ has not. The reactions by which N₂ and H₂ are converted into ammonia in the atmospheres of exoplanets and brown dwarfs are complex and outside the scope of this paper. However, the equilibrium between N₂ and NH₃ favours NH₃ at lower temperatures as (to a lesser extent) do higher pressures. These temperature and pressure dependencies suggest that the outer atmospheres of extrasolar giant planets at large orbital distances will contain significant quantities of ammonia (Sudarsky, Burrows & Hubeny 2003), and it is likely that NH₃ will soon be confirmed to be present in these objects.

Before BYTe, there was no NH₃ line list that was sufficiently complete and accurate for use in modelling the atmospheres of exoplanets, brown dwarfs or other astronomical objects at elevated temperatures. Many astronomers have used the experimental NH₃ line list of Irwin et al. (1999), which covers the 4000–11 000 cm⁻¹ spectral region, even though this line list is only designed to be used at temperatures below 300 K. The high resolution transmission (HITRAN) data base (Rothman et al. 2009) has been also extensively used. This contains approximately 30 000 lines of ¹⁴NH₃, but it too is only suitable for use at ambient temperature, or below, and

*E-mail: j.tennyson@ucl.ac.uk

even then is lacking data in significant regions of the spectrum; we recently demonstrated this using our computed, comprehensive line list for cold NH_3 (Yurchenko et al. 2009). This line list comprises 3.25 million transitions between 184 400 levels. It has an upper energy cut-off of $12\,000\text{ cm}^{-1}$ and a maximum rotational quantum number $J = 20$. However, despite having many more lines than any other NH_3 list, like those other lists, it was designed for use at temperatures up to 300 K, which renders it unsuitable for most astronomical applications. This problem is overcome by BYTe.

2 THE BYTE LINE LIST

BYTe is a catalogue of transitions represented by frequencies, Einstein coefficients, energy levels and quantum numbers, which together fully characterize the electric dipole transitions of the ammonium molecule in the frequency range from 0 to $12\,000\text{ cm}^{-1}$. The list was computed variationally using the program suite TROVE (Yurchenko, Thiel & Jensen 2007). It comprises 1 138 323 351 transitions between 1 373 897 energy levels, all below $18\,000\text{ cm}^{-1}$, and for all J s up to $J = 36$. All transitions are within the ground electronic state of the $^{14}\text{NH}_3$, since the excited electronic states are above the dissociation limit of the molecule. Less than 30 000 NH_3 lines are known experimentally: BYTe contains about 40 000 times as many. It is the most comprehensive and accurate line list of NH_3 and is designed to be applicable at temperatures up to 1500 K.

The ro-vibrational energies and wave functions were computed using a new ‘spectroscopic’ potential energy surface (PES) of NH_3 (Yurchenko et al. 2011). This PES was recently generated through a least-squares fit to the $^{14}\text{NH}_3$ experimental energy levels mostly taken from the HITRAN data base (Rothman et al. 2009). In order to evaluate the Einstein coefficients an *ab initio* (aug-cc-pVTZ) dipole moment surface (DMS) of NH_3 from Yurchenko et al. (2005b) is used. The reported ‘hot’ NH_3 line list is the result of more than three years work by our team. The method of calculation was similar to, but more computer-intensive than, our earlier $T = 300\text{ K}$ NH_3 line list (Yurchenko et al. 2009).

Preliminary versions of BYTe have already been used in several astrophysical studies. In particular, the data have been used in analysing the atmosphere of the late T dwarf UGPS 0722–05 (Lucas et al. 2010) and the atmosphere of the transiting hot Neptune GJ436b (Beaulieu et al. 2011).

3 COMPUTATIONAL DETAILS

The variational rotation–vibration program suite TROVE (Yurchenko et al. 2007) was employed for all nuclear motion calculations required to produce the BYTe line list. This procedure was the same as that used in our cold line list (Yurchenko et al. 2009), and the reader is referred to this earlier paper for a more detailed account of TROVE. The main difference in generating BYTe was that a larger basis set was used than in the case of the cold NH_3 paper.

TROVE normally requires a polyad number P to control the basis set. In the case of ammonia, we define

$$P = 2(n_1 + n_2 + n_3) + n_4 + n_5 + \frac{n_6}{2}, \quad (1)$$

where n_i are the quantum numbers associated with the basis functions ϕ_{n_i} , see Yurchenko et al. (2009). Thus, we include in the basis set only those functions ϕ_n for which $P \leq P_{\text{max}}$. P_{max} was set at 14. This optimum value produced converged eigenvalues with the minimum computational demands.

The Hamiltonian matrices were constructed from the ($J = 0$)-contracted basis set (Yurchenko et al. 2009). In order to improve

the agreement of our line frequencies with experiment, the empirical basis set correction (EBSC) was utilized (Yurchenko et al. 2009). Using the EBSC approach, the vibrational energies in the ro-vibrational calculations were replaced by the corresponding experimental band centres, where these are available.

Apart from extending the basis set, we also enlarged (i) the energy range from $E_{\text{max}} = 12\,000\text{ cm}^{-1}$ to $E_{\text{max}} = 18\,000\text{ cm}^{-1}$, (ii) the frequency range from $0\text{--}8000\text{ cm}^{-1}$ to $0\text{--}12\,000\text{ cm}^{-1}$ and (iii) the range of the rotational excitations considered from $J_{\text{max}} = 20$ to 41, respectively. These changes were necessary for the new line list to be sufficiently complete and accurate to enable spectral calculations at temperatures up to $T = 1500\text{ K}$, which is far more demanding than at $T = 300\text{ K}$, which was the temperature criterion adopted in Yurchenko et al. (2009).

The extensions to these key parameters has a huge impact on the computational costs. In the case of BYTe, the largest Hamiltonian matrix to be diagonalized was for $J = 41$ (E -symmetry block) with dimension 183 153. In contrast, the largest Hamiltonian in Yurchenko et al. (2009) was 86 000 at $J = 20$. However, the most elaborate calculations were in the $J = 20\text{--}27$ range. These were characterized not only by large matrix dimensions (80 000–110 000), but also by a large number of roots of the corresponding eigenvalue problems. This is illustrated on Fig. 1, where we show the number of eigenvalues below the $18\,000\text{ cm}^{-1}$ threshold and the dimensions of the E -symmetry matrices for $J = 0 \dots 41$. Using the computer facilities available to us, we could efficiently employ the LAPACK diagonalizer DSYEV for all J below 23. For $J = 24$ and higher, we had to switch to the Lanczos-based iterative diagonalizer PARPACK (Lehoucq, Sorensen & Yang 1998) (a parallelized version of ARPACK). In fact, the DSYEV LAPACK routine allowed us to compute and store all eigenvalues of a given Hamiltonian matrix for $J \leq 23$, beyond the $E_{\text{max}} = 18\,000\text{ cm}^{-1}$ threshold. One can see from Fig. 1 that for $J > 30$, the number roots to be determined in the eigenvalue problem represents only a small fraction of the matrix dimension (less than 10 per cent). This is important for efficient utilization of the iterative Lanczos-type diagonalization approaches. The matrix diagonalization is the most consuming part of line list calculation, both in terms of time and memory.

Using these techniques, we were able to generate all eigenvalues and eigenvectors for values of J up to 41, subject to the energy threshold of $18\,000\text{ cm}^{-1}$. However, only levels below $J = 36$ were taken into the line list because higher J values did not have any




Figure 1. Dimensions of the E -symmetry matrices (squares), the corresponding number of eigenvalues below $18\,000\text{ cm}^{-1}$ (circles) and number of non-zero elements on each row (diamonds).

ro-vibrational states with energies below the threshold for the lower energy states in BYTe of $E_{\text{low}} = 8000 \text{ cm}^{-1}$.

As previously mentioned, in order to compute the eigenvalues and eigenvectors of NH_3 , we employed a new, improved, ‘spectroscopic’ PES, $\text{NH}_3\text{-Y2010}$. This PES was recently generated through fitting to the available experimental data below $J = 8$. It involved adjustments to the analytical representation from Yurchenko et al. (2005c), using the refined PES from this work as a starting point. This refinement was performed using TROVE, which was extended to allow such fitting tasks. The details of the refinement procedure and the new PES $\text{NH}_3\text{-Y2010}$ will be given elsewhere (Yurchenko et al. 2011).




Figure 2. Numbers of levels below 18000 cm^{-1} per each J (lower display) and corresponding transitions for each $J \rightarrow J + 1$ (upper display).

An accurate DMS is a prerequisite for producing accurate line intensities. Tests have shown that these are best taken directly from high quality *ab initio* calculations (Lynas-Gray, Miller & Tennyson 1995). For BYTe, we employed the ATZfc DMS of NH_3 from Yurchenko et al. (2005b) in the improved DMS representation from Yurchenko et al. (2009), which behaves well when the molecule adopts a planar geometry. This DMS has been shown to provide intensities in good agreement with experiment (Yurchenko et al. 2005b, 2009); it was also used in producing the ‘cool’ ammonia line list (Yurchenko et al. 2009).

To speed up the computation of the transition moments used to generate the Einstein A coefficients, we used the pre-screening procedure, see Yurchenko et al. (2009), in which only eigen-coefficients with magnitude larger than 10^{-12} were selected. This reduced the size of the vectors (by about 70–80 per cent) as well as the computation time. We also imposed an absorption intensity threshold $10^{-12} \text{ cm mol}^{-1}$ ($1.7 \times 10^{-36} \text{ cm/molecule}$) at $T = 1500 \text{ K}$, for the intensities to be included in BYTe. This threshold corresponds to about 10^{-16} of the maximum intensity at $T = 1500 \text{ K}$ ($18000 \text{ cm mol}^{-1}$). The major bottleneck in these calculations was associated with the need to read repeatedly a huge number of eigenvectors stored on the disk. The large size of these vectors prevented us from keeping all of them in the virtual memory during the computational process. We were able to reduce the number of readings by optimizing the computational logistics. In intensity simulations, each transition can be independently processed, which effectively naturally parallelizes them, distributing them between computational nodes (see Yurchenko et al. 2009).

The most expensive part of the intensity calculations was for J from 10 to 20, which accounts for approximately 75 per cent of all transitions to be computed. In Fig. 2 we show how the number of lines and energy levels depend on J . The number of levels peaks

Table 1. Extract from the BYTe Energy file.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
N	J	Γ	N_{block}	Term value	n_1	n_2	n_3	n_4	l_3	l_4	τ_{inv}	J	K	τ_{rot}	v_1	v_2	v_3	v_4	v_5	v_6	Γ_{vib}
1	0	1	1	0.000000	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
2	0	1	2	932.438362	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	2	1
3	0	1	3	1597.487235	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	4	1
4	0	1	4	2384.162466	0	3	0	0	0	0	0	0	0	0	0	0	0	0	0	6	1
5	0	1	5	3215.999346	0	0	0	2	0	0	0	0	0	0	0	0	0	0	2	0	1
6	0	1	6	3336.068662	1	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1
7	0	1	7	3462.472133	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	8	1
8	0	1	8	4115.619903	0	1	0	2	0	0	0	0	0	0	0	0	0	0	2	2	1
9	0	1	9	4294.521388	1	1	0	0	0	0	0	0	0	0	0	1	0	0	0	2	1
10	0	1	10	4695.218516	0	5	0	0	0	0	0	0	0	0	0	0	0	0	0	10	1

Column Notation

1	N	Level number (row)
2	J	Rotational quantum number, angular momentum
3	Γ	Total symmetry in $D_{3h}(M)$
4	N_{block}	Level number in a block
5	E	Term value (in cm^{-1})
6...9	$n_1 \dots n_4$	Normal mode vibrational quantum numbers
10, 11	l_3, l_4	Vibrational angular momenta, normal mode vibrational quantum
12	τ_{inv}	Inversional parity (0,1)
13	J	Rotational quantum number (the same as column 2)
14	K	Rotational quantum number, projection of J on to the z -axis
15	τ_{rot}	Rotational parity (0,1)
16...21	$v_1 \dots v_6$	Local mode vibrational quantum numbers (see Yurchenko et al. 2009)
22	Γ_{vib}	Symmetry of the vibrational contribution in $D_{3h}(M)$

Table 2. Extract from the BYTe Transition file.

N''	N'	A/s^{-1}
8851	5949	1.5609E-03
8852	5949	5.4877E+00
8853	5949	3.3242E-01
8854	5949	2.7161E+00
8855	5949	4.4509E-02

at $J = 15$ and then reduces gradually with higher J and eventually reaches zero due to our lower and upper energy limits of 8000 and 18 000 cm^{-1} , respectively.

4 STRUCTURE OF THE LINE LIST OF NH_3

The BYTe $^{14}\text{NH}_3$ line list contains 1.138 billion lines, which are the allowed transitions above a certain minimum intensity, between 1.367 million ro-vibrational levels. The structure of BYTe is similar to that of the BT2 water line list (Barber et al. 2006). BYTe comprises two files. One, the Energy file, holds the energies and ro-vibrational quantum numbers of all NH_3 states up to $J \leq 41$ that are less than 18 000 cm^{-1} above the zero-point energy (our value is 7430.288 276 cm^{-1}). Table 1 gives an extract from the Energy file. Apart from the general quantum numbers associated with the molecular group symmetry Γ (Bunker & Jensen 1998) [NH_3 belongs to $\mathcal{D}_{3h}(\text{M})$] and total angular momentum J , we have used both ‘normal mode’ and ‘local mode’ quantum numbers when labelling the energy levels. Our labelling scheme is discussed below.

The structure of the Transition file is simpler. It contains three columns: two give the reference numbers of the upper and lower states as they appear in the Energy file and third contains the Einstein A coefficient (s^{-1}) for the transition (see Table 2). The entries in the Transition files are sorted according to the frequency, and we have split them into 120 small files in order to reduce the amount of

data that needs to be handled when examining a specific frequency region.

In the actual TROVE calculations, we employed ‘local mode’ basis functions in the FBR representation as explained in detail in Yurchenko et al. (2009). This allowed us to label the energy levels and hence to assign transitions based on the particular basis set making the largest contribution within the appropriate eigenfunction. Our local mode quantum numbers include $\Gamma_{\text{rot}}, K, \tau_{\text{rot}}, \Gamma_{\text{vib}}, n_1, n_2, n_3, n_4, n_5, n_6$. Here K is the projection of total angular momentum on to the molecular symmetry axis; n_1, n_2, n_3 are stretching local mode quantum numbers (Mills & Robiette 1985) which correlate with the normal mode notation as $n_1 + n_2 + n_3 = \nu_1 + \nu_3$; n_4 and n_5 are deformational bending quanta; n_6 is the inversion quantum number equivalent to $2\nu_2 + \tau_{\text{inv}}$, where ν_2 is the normal mode quantum number and $\tau_{\text{inv}} = n_6 \bmod 2$ is the inversion parity (Yurchenko et al. 2005a). Finally, Γ_{rot} and Γ_{vib} are the rotational and vibrational symmetries in $\mathcal{D}_{3h}(\text{M})$.

Apart from the ‘local mode’ assignment that is generated by TROVE, we also provide the standard normal mode quantum numbers $\nu_1, \nu_2, \nu_3^l, \nu_4^l$, according with the Herzberg convention (Herzberg 1945). ν_1 and ν_2 are the symmetric stretch and symmetric bend, respectively, whilst ν_3 and ν_4 are the asymmetric stretch and asymmetric bend, respectively. The additional quantum numbers l_3 and l_4 are necessary to resolve the degeneracy of the ν_3 and ν_4 vibrational states, respectively.

The selection rules which determine the allowed electric dipole transitions of $^{14}\text{NH}_3$ are $\Delta J = J' - J'' = 0, \pm 1$ ($J'' + J' \geq 1$) with symmetry selection rules, $A'_2 \leftrightarrow A''_2$ and $E' \leftrightarrow E''$. We used the nuclear spin statistical weight factor $g_{\text{ns}} = 12$ and 6 for the $A'_2 \leftrightarrow A''_2$ and $E' \leftrightarrow E''$ transitions, respectively. The A'_1 and A''_1 levels are characterized by $g_{\text{ns}} = 0$, that is, the corresponding transitions do not exist.

It should be noted that our assignments do not always agree with the experimental ones for the following reasons: (i) ambiguous definition of the quantum numbers (apart from J and Γ), which depend on the basis functions used; (ii) strong interactions between




Figure 3. The partition functions $Q_{J_{\text{max}}}$ of NH_3 at different temperatures versus the maximum J value used in equation (2), J_{max} (upper display) and corresponding contributions $(Q - Q_{J_{\text{max}}})/Q$ (per cent), where $Q = Q_{J_{\text{max}}=41}$.

ro-vibrational states of close-lying levels and (iii) mapping between the normal and local mode labels is not always straightforward. The last of these means that it is sometimes difficult to distinguish between the symmetric and asymmetric stretch quantum numbers v_1 and v_3 .

5 LINE LIST: DESCRIPTION AND VALIDATION

Absorption and emission intensity simulations are temperature-dependent. Specifically, temperature appears in the Boltzmann factors $\exp(-E/kT)$, where k is the Boltzmann constant. Line lists, in contrast, do not specify a temperature, since the Einstein coefficients for the transitions are independent of temperature. We therefore need to explain why we refer to BYTe as a ‘hot’ list. The reason is that BYTe is able to describe the absorption/emission processes

in NH_3 for temperatures up to $T_{\max} = 1500$ K. This is because the energy threshold that we have adopted, $E_{\text{low}} = 8000$ cm^{-1} , ensures that we include all those states that are significantly populated up to $T = T_{\max}$.

The temperature coverage of our data can be conveniently checked by using it to compute temperature-dependent partition functions for NH_3 .

$$Q = \sum_j g_j \exp(-E_j/kT), \quad (2)$$

where g_j is the total degeneracy of the state with energy E_j and the sum runs over all energy levels of the molecule. Including all energy levels up to 8000 cm^{-1} gives an NH_3 partition function, Q , of 57 944 at $T = 1500$ K. This value is about 5 per cent below our best estimate for Q at 1 500 of 61 223. This discrepancy, which rapidly disappears at lower temperatures, is the reason we do not recommend the use of BYTe for temperatures above 1500 K.

Apart from E_{low} , there are two main contributions that affect the total number of the excited ro-vibrational states accessed in the variational calculations: (i) the size of the vibrational basis set, which BYTe is determined by the polyad number P_{\max} (see equation 1) and (ii) the size of the rotational basis set, determined by the maximal total angular momentum J_{\max} . Fig. 3 illustrates how the partition function of NH_3 depends on J_{\max} for $T = 300$ K, 600 K, 900 K, 1200 K and 1500 K (upper display). For $T = 1500$ K, the contribution to Q from $J > 30$ amounts to less than 1 per cent, see lower display of Fig. 3, where the relative contributions $(Q - Q_{J_{\max}})/Q$ to the partition function are also shown as percentages. Here we used $Q = Q_{J_{\max}=41}$, where $J_{\max} = 41$, corresponding to the highest J in our variational calculations.

The effect of the vibrational basis set on the partition function is less pronounced: at $T = 1500$ K and $J_{\max} = 35$, the partition function is converged to better than 0.03 per cent when testing our choice of basis set size. There are, of course, other factors that give rise to errors in our computed partition functions. One of these is




Figure 4. Absorption spectra of NH_3 given by BYTe for $T = 300, 600, 900, 1200$ and 1500 K, convoluted with a Gaussian profile, half width at half-maximum, $\text{HWHM} = 0.5$ cm^{-1} .




Figure 5. BYTe absorption spectra of NH_3 for $T = 300, 600, 900, 1200$ and 1500 K, convoluted with a Gaussian profile, $\text{HWHM} = 5$ cm^{-1} : the 3-, 2-, 1.5- and 1.25- μm regions.




Figure 6. Absorption spectra of NH_3 at $T = 300 \text{ K}$ (cm mol^{-1}): BYTe versus HITRAN.

the potential energy function, which is only reasonably accurately fitted to low-lying ro-vibrational levels. We will address the nature of the partition function of ammonia in greater details elsewhere.

Figs 4 and 5 illustrate the T -dependence of the absorption spectra of ammonia, and give an overview of the complete range as well as of the four selected regions computed at $T = 300, 600, 900, 1200$ and 1500 K . As expected, the spectrum profiles at higher T become less extreme as the populations from the lower vibrational states are reduced in favour of the vibrationally excited states. Only those few bands that are the most pronounced features at $T = 300 \text{ K}$ are still recognizable at $T = 1500 \text{ K}$.

Our ‘cold’ NH_3 paper (Yurchenko et al. 2009) contained detailed comparisons with the HITRAN data base (Rothman et al. 2009) which demonstrated the accuracy of our procedure and also, that even at 300 K , HITRAN is missing significant NH_3 data. In BYTe, we have improved our ability to reproduce the HITRAN data, see Fig. 6; however we do not show the entire comparison here.

As we were completing our calculations, a high-temperature emission spectra of ammonia ($T = 900 \text{ K}$) for the ground and ν_2 states of ammonia was reported by Yu et al. (2010). We use this spectrum to provide an independent validation of the BYTe line list. To this end we used BYTe to generate a 900 K synthetic emission spectrum of NH_3 in the same spectral region. This is shown in Fig. 7 (lower part). The ‘experimental’ spectrum on this figure was generated using the Einstein coefficients from the synthetic line list reported by Yu et al. (2010). The spectra agree not only qualitatively but also quantitatively in terms of the absolute intensity values. The additional lines in the upper part of Fig. 7 are present because our synthetic spectrum includes all possible transitions falling into the region including hot bands, while Yu et al.’s data are only for the ground and ν_2 states of NH_3 .

6 CONCLUSION

We have calculated to a high level of accuracy the frequencies and Einstein A coefficients of all the transitions that are present in the emission and absorption spectrum of NH_3 . The only limitations are as follows: upper states with energies above 18000 cm^{-1} are




Figure 7. Emission spectra of NH_3 at $T = 900 \text{ K}$ ($\text{erg molecule}^{-1} \text{ Sr}^{-1}$). The ‘experimental spectrum’ (lower display) is reconstructed using the Einstein coefficients from Yu et al. (2010).

excluded; there is an effective short-end wavelength cut-off of $1 \mu\text{m}$, due to the incompleteness of our data at frequencies above 10000 cm^{-1} (the excluded region is unimportant for NH_3), and extremely weak lines have been excluded, which is of little physical significance.

Although the BYTe line list is explicitly aimed at modelling hot ammonia, it improves on our previous cold line list (Yurchenko et al. 2009) in terms of the quality of the PES used, in the size of the basis sets employed and in the range of frequencies studied. We therefore recommend the use of BYTe for all temperatures up to 1500 K . The line list is freely available and can download in its entirety or in parts from the Strasbourg data repository via <ftp://cdsarc.u-strasbg.fr/pub/cats/VI/133> or from www.exomol.com website where the line list will be maintained.

ACKNOWLEDGMENTS

We thank members of UCL’s Research Computing who have supported this work by giving us extended access to both the Legion and Unity high performance computing systems. We are also

grateful to Shanshan Yu for providing her results prior to publication. We thank the Leverhulme Trust for funding this work and STFC for support via a grant to the ‘Miracle’ computing consortium.

REFERENCES

- Barber R. J., Tennyson J., Harris G. J., Tolchenov R. N., 2006, *MNRAS*, 368, 1087
- Barber R. J., Miller S., Dello Russo N., Mumma M. J., Tennyson J., Guio P., 2009, *MNRAS*, 398, 1593
- Beaulieu J.-P. et al., 2011, *ApJ*, in press
- Bonev B. P., Mumma M. J., Gibb E. L., DiSanti M. A. G. L., Villanueva Magee-Sauer K., Ellis R. S., 2009, *ApJ*, 699, 1563
- Bunker P. R., Jensen P., 1998, *Molecular Symmetry and Spectroscopy*, 2nd edn. NRC Research Press, Ottawa
- Burrows A. et al., 1997, *ApJ*, 491, 856
- Burrows A., Sudarsky D., Lenine J. I., 2003, *ApJ*, 596, 587
- Dello Russo N., DiSanti M. A., Magee-Sauer K., Gibb E. L., Mumma M. J., Barber R. J., Tennyson J., 2004, *Icarus*, 168, 186
- Fletcher L. N., Orton G. S., Lisse C. M., Edwards M. L., de Pater I., Yanamandra-Fisher P. A., Fisher B. M., Hammel H. B., 2011, *Icarus*, 211, 568
- Herzberg G., 1945, *Infrared and Raman Spectra of Polyatomic Molecules*. D. Van Nostrand Co. Inc., New York
- Irwin P., Calcutt S., Sihra K., Taylor F., Weir A., Ballard J., Johnston W., 1999, *J. Quant. Spectrosc. Radiative Transfer*, 62, 193
- Kawakita H., Mumma M. J., 2011, *ApJ*, 727, 91
- Kawakita H., Watanabe J. I., 2002, *ApJ*, 572, L17
- Lara L. M., Bézard B., Griffith C. A., Lacy J. H., Owen T., 1998, *Icarus*, 131, 317
- Lehoucq R. B., Sorensen D. C., Yang C., 1998, *ARPACK Users’ Guide: Solution of Large-scale Eigenvalue Problems with Implicitly Restarted Arnoldi Methods (Software, Environments and Tools)*. Society for Industrial and Applied Mathematics, USA (<http://www.caam.rice.edu/software/ARPACK/>)
- Lucas P. W. et al., 2010, *MNRAS*, 408, L56
- Lynas-Gray A. E., Miller S., Tennyson J., 1995, *J. Molecular Spectrosc.*, 169, 458
- Madden S. C., Irvine W. M., Matthews H. E., Brown R. D., Godfrey P. D., 1986, *ApJ*, 300, L79
- Mills I., Robiette A., 1985, *Molecular Phys.*, 56, 743
- Orton G. et al., 1995, *Sci*, 267, 1277
- Orton G. S. et al., 2011, *Icarus*, 211, 587
- Rothman L. S. et al., 2009, *J. Quant. Spectrosc. Radiative Transfer*, 110, 533
- Sharp C. M., Burrows A., 2007, *ApJS*, 168, 140
- Sudarsky D., Burrows A., Hubeny I., 2003, *ApJ*, 588, 1121
- Swain M. R., Vasisht G., Tinetti G., 2008, *Nat*, 452, 329
- Tinetti G. et al., 2007, *Nat*, 448, 169
- Yu S. et al., 2010, *J. Chemical Phys.*, 133, 174317
- Yurchenko S. N., Carvajal M., Jensen P., Lin H., Zheng J. J., Thiel W., 2005a, *Molecular Phys.*, 103, 359
- Yurchenko S. N., Carvajal M., Zheng J., Thiel W., Jensen P., 2005b, *J. Chemical Phys.*, 122, 104317
- Yurchenko S. N., Zheng J. J., Lin H., Jensen P., Thiel W., 2005c, *J. Chemical Phys.*, 123, 134308
- Yurchenko S. N., Thiel W., Jensen P., 2007, *J. Molecular Spectrosc.*, 245, 126
- Yurchenko S. N., Barber R. J., Yachmenev A., Thiel W., Jensen P., Tennyson J., 2009, *J. Phys. Chemistry A*, 113, 11845
- Yurchenko S. N., Barber R. J., Tennyson J., Thiel W., Jensen P., 2011, *J. Molecular Spectrosc.*, submitted

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.